Estimate for Face Lifting work of 2 nos N-Type (N5-N6) staff qtr of ESIH Gourhati.

Sl. No.	Item No.	Description of Item Dismantling old plaster or skirting	Unit	Qnty	Rate	Amount Rs.
1	P-253 15.56	ranking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 meters lead.	Sqm	1600		
2	P-237 14.1	15mm Cement plaster on the rough side of single or hall brick wall of mix 1 : 4 (1Cement : 4 coarse sand)	Sqm	1600		
3	P-248 15.3	Demolishing RCC work manually by mechanical means including stacking of steak bars and disposal of unserviceable material within 50 meters lead as per direction of engineer-n-charge	Cm	6		
4	P-251 15.42	Dismantling C.I. or asbestos rain water pipe with fitting and clamps including stacking the materials within 50 meters lead 100 meters dia pipe Reinforced cement concrete work	Mtrs	255		
5	P-96 5.2.2	in walls (any thickness) including attached plasters buttresses, plinth and string courses fillers columns pillars piers abutments posts and struts etc upto floor five level excluding cost of centering shuttering finishing and reinforcement 1:1.5:3 (1 Cement: 1.5 coarse sand: 3 graded stone aggregate 20mm normal size)	Cm	6		
6	P-291 17.35.2.1	Providing and fixing soil, waste and went pipes 100mm	Meter	255		
7	P-147 9.1.2	Providing wood work in frames for doors, window, clerestory windows and others framers wrought framed and fixed in position. Sal Wood. Providing and fixing paneled and	Cu.m	3.5		
8	P-147 9.1.2	glazed shutters for doors windows and clerestory windows including SIS marked black enameled M.S. butt hinges with necessary screws including paneling which will be paid separately 35mm thick shutters.	Sq.m.	90		

		Painting (two or more) on rain			
9	P-147 9.5.1	Painting (two or more) on rain water soil waste and vent pipes and fittings with synthetic enamel paints required colour over a priming coat of approval steel primer on new work 100mm diameter pipes.	Mtr	450	
10	P-156 9.70.1	Providing and fixing IS:12817 marked stainless steel butt hinges with stainless steel screws etc. Complete 250x64x1.90 mm	Each	288	
11	P-157 9.74.1	Providing and fixing bright finished brass tower belts (barrel type) with necessary screws etc complete 250 x 10 mm239073.41	Each	160	
12	P-225 13.46.1	Finishing walls with Acrylic smooth exterior paint of required shade new work (two or more coats applied @ 1.67 Lts/ 10 Sq.m.) over and including priming coat of exterior primer applied @ 2.20kg / 10 Sq.m.	Sq.m	2050	
13	P-2226 13.48.2	Painting wood work with deluxe multi surface paint of required shade. Tower or more coat applied @ 0.90 Lts 10 Sq.m over an under coat of primer applied @ 75 Ltr/ 10 Sq.m. of approved brands of manufacture.	Sq.m	290	
14	P-97 5.9.3	Centering and shuttering including strutting propping etc and removal of form suspended floors landing. Providing and fixing M.S. grill of	Sq.m	195	
15	P-179 10.25.2	required pattern in frames of windows etc with M.S. flats squares or round bars etc. All complete fixed to opening / wooden frames with rawl plugs etc.	Kg	480	
16	P-180 10.30	Providing and fixing glass panes with putty and glazing clips in window (4 mm.)	Sq.m	45	
17	P-176 10.3	Providing and fixing position collapsible steel shutters with vertical channels 20 x 10 x 2mm and braced with iron diagonals 20 x 5 mm size with top and bottom rail.	Sq.m	7	

Total Rs.

Rate Offered By The Agency	
In Figures	
In Words	